

1-5

2-040756

R

RECEIVED  
KANSAS CORPORATION COMMISSION  
1-19-93  
JAN 19 1993

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

15-077-20554-00-00

API NUMBER: 10/10/79  
App SW NE NE , SECTION 30 TOWNSHIP 32 RANGE 8W

OPERATOR LICENSE # 5171 4340 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

OPERATOR Marathon  
NAME & RR #1, Box 125B  
ADDRESS Medicine Lodge, KS 67104

LEASE NAME: Robinson C-1  
COUNTY: Harper 162.50  
WELL TOTAL DEPTH: 5000' PA 3795'

CONDUCTOR PIPE: 13-3/8" @ 84'  
SURFACE CASING: 8-5/8" @ 350'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ DEA \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Clarke Corp.  
ADDRESS: Medicine Lodge, KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Elmo Morgenstien  
COMPANY NAME: Clark Corporation PHONE: \_\_\_\_\_

WERE: 2-7/8" @ 3822' - perfs 3672-3694' - PBDT 3795' - 20  
sx 3300' - recover pipe - 35 sx 1325' - 35 sx 850'  
- circ cmt 400'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1330 DAY: 5 MONTH: 1 YEAR: 1993

ACTUAL PLUGGING REPORT:  
20 sx cmt plug pushed to 3300' to close perfs -  
2-7/8" shot loose @ 2485' & pulled to 1343' & 35 sx  
cmt spotted - tub pulled to 853' & 35 sx cmt spotted  
- 2-7/8" pulled to 396' & cmt circ to surf.

REMARKS: Allied 3398 60/40 4% gel 0 poz

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 1-25-93  
INV. NO. 37243

HS  
Steve Van Gieson (AGENT)

FORM CP-2/3  
REV. 3/90

aw