

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

3-3

A PI NUMBER: 15-077-20810-00-00

C-NW NW, SECTION 30 TOWNSHIP 32S RANGE 8 W
OPERATOR LICENSE # 5506 4620 FEET FROM S SECTION LINE
OPERATOR Woolsey Petroleum Corp 4620 FEET FROM E SECTION LINE
NAME & 1966 S E Rodeo Dr P O Box 168
ADDRESS Medicine Lodge, Ks. 67104 LEASE NAME: Antrim A-2
COUNTY: Harper
WELL TOTAL DEPTH: 4050 131.63
PIPE: 4 1/2" e 404 9
SURFACE CASING: 8 5/8" 253 Feet

ABANDONED OIL WELL ___ GAS WELL XX INPUT WELL ___ SWD ___ D&A ___

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clark Well Service

ADDRESS: 107 Fowler Ave Medicine Lodge, Ks 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 3rd MONTH: March YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Carl Durr

COMPANY NAME: Woolsey Petroleum Corp PHONE: 316-886-5606

WERE: Sand back 50' above perfs. with 4 sacks on top of sand. Pull casing. Run tubing to 1325 w/35 sacks, pull to 830' with 35 sacks, pull to 310' with cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 16 1999
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING PROPOSAL RECEIVED BY: KCC

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (XX)

COMPLETED: HOUR: 13:00 DAY: 3rd MONTH: March YEAR: 1999

ACTUAL PLUGGING REPORT: Sand back to 3560' with 4 sacks cement on top of sand. Pull casing to surface. Run tubing to 1325' with 35 sacks cement. Pull to 830' with 35 sacks cement. Pull to 310' with 130 sacks cement to surface. 60/40 poz with 4% gel

REMARKS: Allied Cementing # 9815

I DID NOT OBSERVE THIS PLUGGING.


Donald Hoberecht

INVOICED
DATE 3-18-99
INV. NO. 60732