

2 040328

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,449 - 60-61

C SW , SEC. 30, T 32 S, R 8 W/RX

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Antrim Well # 1

Operator: TXO Production Corporation

County Harper 157.66

Name & Address 155 North Market, Ste. 1000

Well Total Depth 4851 PBDT 3500 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Pratt, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Jeff

(company name) TXO Production Corporation (phone)

were: 4 1/2" set at 4552'. Perforated from 3427-29. Sand to 4370' and dump four sacks cement. Pump 2 hulls, 15 gel and 150 sacks.

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:15 Day: 29 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2" casing to 4370' and capped with

four sacks cement. The 4 1/2" was recovered from 4370'. The top was

squeezed with two sacks of hulls, 15 sacks of gel and 150 sacks of

60/40 poz, 2% gel.

RECEIVED
STATE CORPORATION COMMISSION

5-6-87
MAY 6 - 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: B.J.Titan #2848707 MX - 800# SI - 600#

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-87

Signed St. O. [Signature]
(TECHNICIAN)

INV. NO. 16839