

6-30

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-060213

API Number: 15-077-20,952-00-00

C SE NE SECTION 26 TWP 32 RANGE 08W

OPERATOR LICENSE # 5506
OPERATOR WOOLSEY PETROLEUM CORP.
NAME & P.O. BOX 168
ADDRESS MEDICINE LODGE, KS 67104

3300 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

LEASE NAME SLAGELL #A-1
COUNTY HARPER
WELL TOTAL DEPTH 3945' PB 3900' 128.22
PIPE 4 1/2" @ 3940'
SURFACE CASING 8 5/8" @ 266'

ABANDONED OIL WELL _____ GAS WELL _____ X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: PERF 3652-66'

PLUGGING CONTRACTOR: CLARKE CORPORATION

ADDRESS: 107 WEST FOWLER, MEDICINE LODGE, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: _____ HOUR: 10:00 DAY: 30 MONTH: 6 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: CARL DURR

COMPANY NAME: CLARKE CORPORATION

WERE: _____

PHONE (316) 886-5665
RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 1998
7-2-98
CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: DOUG LOUIS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL _____ PART X NONE _____

COMPLETED: HOUR: 11:10 DAY: 30 MONTH: 6 YEAR: 1998

ACTUAL PLUGGING REPORT: SAND BACK TO 3500'. CAP WITH 4 SACKS CEMENT THROUGH DUMP BAILER. SHOT 4 1/2" CASING OFF @2800' AND PULL FROM WELL BORE. RUN TUBE BACK INTO 1204', SPOT 35 SX CEMENT. PULL TO 790', SPOT 35 SX CEMENT. PULL TO 317' AND CIRCULATE CEMENT TO SURFACE.

REMARKS: ALLIED CEMENT #9631, 60/40 POZ, 4% GEL

I DID OBSERVE THIS PLUGGING.

Dave Wertz
DAVE WERTZ

INVOICED

DATE JUL 07 1998

INV. NO. 50873

FORM CP-2/3
REV. 3/90