

6-5

2-070289

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 15-077-20,899-00-00  
NE, SECTION 26 TOWNSHIP 32 RANGE 08W

OPERATOR LICENSE # 5003 FEET FROM S SECTION LINE  
FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corporation  
NAME # 110 South Main, #500  
ADDRESS Wichita, KS 67202

LEASE NAME: Slagell "A" #1  
COUNTY: Harper  
WELL TOTAL DEPTH: 3952' - 128.74  
CONDUCTOR PIPE: " @ "  
SURFACE CASING: 8-5/8" @ 262'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_  
OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Hayes Well Service

ADDRESS: Attica, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 5 MONTH: 6 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Darrell  
COMPANY NAME: McCoy Petroleum Corporation PHONE: \_\_\_\_\_

WERE: Set cast iron bridge plug at 3600' 2 sx - 25 sx at 1270' - 25 sx at 820' - 316' to surface.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gleason

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 7:00 DAY: 5 MONTH: 6 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Set cast iron bridge plug at 3600' - ran 2 sx of common on top of it - shot 4-1/2" casing off at 2113' - pulled to 1270' & pumped 25 sx - pulled to 820' - pumped 25 sx - pulled to 316' - pumped to surface.

REMARKS: Halliburton #904148 60/40 6%

I DID OBSERVE THIS PLUGGING: Steve Van Gleason

Jack Luthi  
Jack Luthi (AGENT)

JUN 13 1990

INVOICED

DATE 6-25-90

INV. NO. 28459

FORM CP-2/3  
REV. 3/90