

15-007-10305-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 19 Twp. 33S Rge. (E) 13 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines NW/4 NE/4 SW/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Lasswell Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 8 19 55
Application for plugging filed February 2 19 60
Application for plugging approved February 4 19 60
Plugging commenced February 9 19 60
Plugging completed February 18 19 60
Reason for abandonment of well or producing formation Depleted reservoir

If a producing well is abandoned, date of last production January 20 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie, Kansas
Producing formation Massey Depth to top _____ Bottom _____ Total Depth of Well 4660' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	none
				5-1/2"	4660	3900

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4580 ft., mixed and ran
5 sx. cement with dump bailer, Mud to 250 ft.,
set 10 ft. rock bridge with 20 sx. cement,
mud to 35 ft., set 10 ft. rock bridge with
10 sx. cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1960
3-29-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company - License No. 12
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March 19 60
Barbara J. Scott
Barbara J. Scott, Notary Public.

My commission expires December 1, 1960

NO. 1 LASSWELL

WELL RECORD

Location: NW NE SW, 19-33S-13W
Barber County, Kansas

Operator: Gramehart-Miller Oil Company
1005 East Second, Wichita, Kansas

Contractor: Graham-Messman-Rinehart Oil Co.
1005 East Second, Wichita, Kansas

Commenced: May 6, 1955

Completed: May 22, 1955

Elevation: 1783 KB

Production: Oil

.....L O G.....

Surface Clay and Shale	45
Shale-Sand Streaks	200
Shale-Shells	260
Shale-Sand Streaks	395
Shale	715
Anhydrite	760
Shale	980
Shale-Shells	1535
Shale-Lime Streaks	1610
Lime-Shale	1875
Shale-Lime	2027
Lime-Shale	2545
Shale-Lime	2614
Lime-Shale	2750
Shale-Lime Streaks	2900
Lime-Shale	3924
Lime	4035
Lime-Shale-Sand Streaks	4130
Lime-Shale	4173
Lime	4525
Lime-Shale Streaks	4575
Lime	4675
Chert-Lime	4706
Lime-Chert	4746
Lime	4760 R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1960
3-29-60
CONSERVATION DIVISION
Wichita, Kansas

Sample Tops:

Heebner 3944 (-2161)
Lansing 4126 (-2343)
Miss. 4656 (-2873)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 9th day of June 1955.

Frank L. Lewis Notary Public
My Commission Expires: November 5, 1958



NO. 1 LASSWELL

LOCATION: NW NE SW, 19-33S-13W
Barber County, Kansas

SUPPLEMENTAL REPORT: Cable Tool Unit Activity

R.T.D. 4760 5½" at 4660

Moved in cable tools June 4, 1955, and drilled out cement to 4635.

Perf 4605-14' with 48 shots. Swb 7½ BO 1st hr, 3 BOPH next 2½ hrs, and 1 BO next hr, natural.

Acidized with 2000 gals. Swb 14 BO, trace wtr 1st hr and 4 BO with trace wtr the 8th hr. Tested app 36 hrs. Last hr swb 2 BO, no wtr, some gas.

Acidized with 4000 gals (2000 Gel-acid followed by 2000 regular.) Started swb 7 BPPH, 18% wtr. Decreased in 3 hrs to 4 BO, 4% wtr.

Swb 4 BOPH, 4% wtr for 8 hrs. Ran tbg and rods. Will install pumping equipment. Completed 6-8-55.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1960
3-29-60
CONSERVATION DIVISION
Wichita, Kansas