

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-007-00079-0000 Compl.

API NUMBER None issued/8-17-5

LEASE NAME LENKNER

WELL NUMBER #1

3630' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 19 TWP. 33S RGE. 13W XXXXX (W)

COUNTY Barber

Date Well Completed 8/1/55

Plugging Commenced 5/22/86

Plugging Completed 5/22/86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR MULL DRILLING COMPANY, INC.

ADDRESS P.O. Box 2758, Wichita, KS 67201

PHONE# (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Jack Luthi

Is ACO-1 filed? 6/3/86 If not, is well log attached? No logs run  
(4621-4630)

Producing Formation Marmaton Depth to Top 4597 Bottom 4630 T.D. 4673'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	273	8-5/8"		
		0	4722	5-1/2"		510' ripped pipe @ 510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

5/19/86 Pld tbg & rods. 5/20/86 Sanded off bttm 5 1/2" from 4722-4570'  
Dmpd 5 sx cement. Rlsd rig. 5/21/86 Ripped 5 1/2" pipe @ 510'. Pld 510'.  
Rlsd rig. Used 100# hulls, 65 sx 40-60 poz & 2% gel. Surf pipe press. to  
1300#. P&A 11:00 AM. Jack Luthi State Plugger.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address \_\_\_\_\_

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Paul M. Gunzelman (Employee of Operator) or ~~XXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul M. Gunzelman

(Address) P.O. Box 2758, Wichita 67201

SUBSCRIBED Paul M. Gunzelman before me this 3rd day of June, 19 86

PATRICIA L. UNGLEICH  
 STATE NOTARY PUBLIC  
 Sedgwick County, Kansas  
 My Appt. Exp. 3/27/87

Commission Expires: March 27, 1987

Patricia Ungleich  
 Notary Public  
 Patricia L. Ungleich

MAILED

NO. 1 LENEXHA

MAY 8 1986

5-8-86

WELL RECORDCONSERVATION DIVISION  
WICHITA, KANSASLocation: NW SW NW, 19-33S-13W  
Barber County, Kansas

Commenced: July 19, 1955

Operator: Purcell-Mull Drilling Co., Inc.  
6405 East Kellogg, Wichita, Kansas

Completed: July 21, 1955

Contractor: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas

Elevation: 1804 KB

Casing Record: 8 5/8" @ 273' w/180 sacks cement  
5 1/2" @ 1724' w/200 sacks cement

Production:

....L O G....

Sand-Red Bed	h0
Red Bed-Shale	1264
Shale	1467
Shale-Lime	2330
Lime-Shale	h063
Sand	h122
Lime	h724 R.T.D.

Sample Tops: (Corrected)

Heobner 3962 (-2148)  
 Toronto 3976 (-2162)  
 Douglas 4002 (-2188)  
 Douglas Sd 4012 (-2198)  
 Brown Lime 4113 (-2329)  
 Lansing 4119 (-2335)  
 Marnton 4591 (-2777)  
 Mississippi 4673 (-2859)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me  
this 8th day of August, 1955.

Quanta L. Loria  
Notary Public

My Commission Expires: November 5, 1958