

15-007-00077-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 22 Twp. 31 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NW 1/4

Lease Owner Orville H. Parker

Lease Name Chain Well No. A 1

Office Address Arkansas City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-19-54 19

Application for plugging filed 12-22-54 19

Application for plugging approved 19

Plugging commenced 12-19-54 19

Plugging completed 12-19-54 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production --- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well

Producing formation None Depth to top - Bottom - Total Depth of Well 4576 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Elgin		3619				
Heebner		3758				
Douglas		3888				
Lansing		3925				
Miss		4521				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Put in heavy mud to bottom of surface pipe, Put 3 # ss of hulls and Halliburton plug at bottom of surface pipe. Put 20 sx of cement then heavy mud within 30' of surface. Put in more hulls and another Halliburton plug. Capped with 10 sx of cement to top of pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor (no pipe set)

Address

STATE OF Kansas, COUNTY OF Cowley, ss.

Thalia Welborn (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thalia Welborn

Ponca City, Okla. (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1955

Katherine Hinton

Notary Public.

My commission expires November 12, 1957

24-2675-S 2-52-20M

PLUGGING
FILE SEC 22 T 31 R 11W
BOOK PAGE 84 LINE 36

2-9-55
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Orville H. Parker
 Chain #1
 Center of NW/4 22-31S-11W
 Barber County, Kansas

CONTRACTOR: SMITHERMAN & COHEN DRILLING CO.
 COMMENCED: 11-27-54
 COMPLETED: 12-12-54

FORMATION

Surf Hole	0- 140	Sand Elgin	3649-3660
Surf Hole	140- 260	Sand Broken	3660-3700
Cement	220- 260	Shale and Sand	3700-3832
Shale Red Rock & Shells	260- 740	Lime and Shale	3832-3887
Shale and Shells	740-1191	Sand	3887-3899
Shale and Shell	1191-1710	Sand	3899-3945
Shale	1710-1725	Lime	3945-3979
Lime Sandy	1725-1940	Lime	3979-4054
Lime and Shale	1940-2067	Lime	4054-4101
Lime W/Shale streaks	2067-2210	Lime	4101-4125
Lime W/S streaks	2210-2325	Lime	4125-4172
Lime W/Shale Streaks	2325-2390	Lime W/Shale streaks	4172-4218
Lime Broken	2390-2505	Lime	4218-4254
Shale and Lime	2505-2570	Lime	4254-4295
Lime and Shale	2570-2670	Lime W/Shale streaks	4295-4328
Shale W/Lime Streaks	2670-2780	Lime	4328-4378
Shale W/Lime Streaks	2780-3000	Lime	4378-4416
Lime W/Shale Streaks	3000-3113	Shale W/Lime Streaks	4416-4470
Lime	3113-3130	Lime W/Shale streaks	4470-4523
Shale and Lime	3130-3215	Chert	4523-4535
Shale and Lime	3215-3320	Lime-Mississippi	4535-4552
Lime	3320-3352	Lime-Mississippi	4552-4556
Shale and Lime	3352-3415	Lime-Mississippi	4556-4574
Lime Sandy W/Shale strks.	3415-3550	Lime	4574-4576
Shale and Sandy Lime	3550-3649	TOTAL DEPTH	4576-

We certify that the above log is true and correct to the best of our knowledge and belief.

SMITHERMAN & COHEN DRILLING COMPANY

BY _____

PLUGGING
 FILE REC 22 31 R 11W
 BOOK PAGE 84 LINE 36

REC
 STATE CORP
 2-5-55
 FEB
 CONSERVATION DIVISION
 Wichita, K