

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name W. C. Pickens

Complete Address: 2000 Fidelity Union Tower, Dallas, Texas

Lease Name Hayes Well No. # 1

Location C NW NE Sec. 30 Twp. 33 Rge. 8 (E) (W) W

County Harper Total Depth 4937'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 7:00AM Day 4th Month Dec. Year 1966

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated with 210 sacks. Hole
was filled with drilling mud to 260', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 260', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/66
INV. NO. 11413-u