

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 072 - 20468 - 00 - 00 (of this well)

Operator's Full Name McCoy Petroleum

Complete Address 316 Vickers KSB&T Bldg., Wichita, Ks. 67202

Lease Name Masner Well No. 1

Location C SE NE Sec. 30 Twp 33s Rge. 8 (E)  (W)

County Harper Total Depth 4556

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 11:30 Am. Day 11 Month 1 Year 1980

The above well was plugged as follows:

240' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4450' w/150  
sax cement. Plug back to 4515' - Preforated at 4491' to 95' - Sand back to  
4450' - Top sand w/4 sax cement w/dump bailer. Pull 3766' 4 1/2" casing -  
Allied mixed & pumped 8 sax hulls - 25 sax gel - 125 sax 50/50 posmix  
cement in 8 5/8" casing to top of casing. Shut in w/400# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 14 1980

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 1-17-80

INV. NO. 1309-w