

JP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 - 1965
8-2-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Continental Oil Company

Complete Address: Box 267, Great Bend, Kansas

Lease Name E. E. Holmes Well No. # 1

Location NE NE NW Sec. 35 Twp. 33 Rge. 13 (E) (W) W

County Barber Total Depth 5038'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 30th Month July Year 1965

The Above well was plugged as follows:

320' of 13 3/8" surface pipe, cemented with 300 sacks. 4514' of 4 1/2" long
string, cemented with 200 sacks. Plug back to 4570'. This is ~~and~~ open hole.
Bottom of the hole was sanded to 4500', and cemented with 3 sacks. 3600' of
4 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge
was pushed in fluid to 250', rock bridge from 250' to 240'. 20 sacks of cemen
was mixed in barrel, and put on plug at 240', through the dump bailer, and
let set over-night. Next morning hole was bailed dry, and 30 sacks of cement
was added to the plug. Hole was filled with mud to 35', rock bridge, and cem-
ented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/2/65

INV. NO. 1567-W