

1 010194

DEC 23 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,941-0000

C NE NW, SEC. 19, T 33 S, R 13 W/E

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9810

Lease Name Gene Bell Well # 1

Operator: T.H. McElvain Oil & Gas Properties
Name &

County Barber 168.19

Address P.O. Box 2148

Well Total Depth 5175 feet

Santa Fe, NM 87504

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:20 a.m. Day: 23 Month: 12 Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4740' PBD 4640' Perfs at 4607-11'

1st plug sand back to 4560' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi and Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 23 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4560' and dumped 4 sx cement on top of sand
through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pump 100 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 250 psi.

DEC 30 1986
12-30-86
CONSERVATION DIVISION
Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3500' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 12-31-86

INV. NO. 15699