

1 040834

3-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA 15-007-10306-0000

C SE, SEC. 19, T 33 S, R 13 W/E

1320 feet from S section line

1320 feet from E section line

Lease Name Laswell Well # 1

County Barber

Well Total Depth 4700 152.75 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 254

Operator License # 6006

Operator: Molz Oil Company

Name

Address RR 2, Box 54

Kiowa, KS 67070

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:15 p.m. Day: 25 Month: 3 Year: 1994

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

vers: 7" at 4678' w/550 sx cement, Open hole 4678-4700'

1st plug sand back to 4620' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 12 sx gel, 50 sx cement, 15 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 25 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4590' and dumped 7 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 12 sx gel, 50 sx cement, 15 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 7" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-6-94

WV. NO. 40324

Signed [Signature] STATE CORPORATION COMMISSION
TECHNICAL DIVISION
Wichita, Kansas

3-30-94
RECEIVED
MAR 30 1994