

1 010141

15-007-00079-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 8-17-55
NW SW NW , SEC. 19 , T 33 S, R 13 W/E

3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Lenkner Well # 1

Operator: Mull Drilling Co., Inc.
Name & Address P. O. Box 2758
Wichita, KS 67201

County Barber 153.47

Well Total Depth 4722' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mull Drilling Co., Inc. License Number 316-264-6366

Address P. O. Box 2758, Wichita, KS 67201

Company to plug at: Hour: 10:30 am Day: 22 Month: May Year: 19 86

Plugging proposal received from Gene Brown

(company name) Mull Drilling (phone) 316-264-6366

were: 5 1/2" at 4722' Perfs at 4620-30'; 4626-30'; 4621-27'

1st plug sand back to 4570' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, and 150 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:05 am Day: 22 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4572' and dumped 5 sx cement on top of sand through bailer. 2nd plug squeezed well with 2 sx hulls and 70 sx cement.

Maximum pressure 1500 psi and shut in 1000 psi

Remarks: Recovered 510' 5 1/2" casing. Used Halcolite by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
JUN 02 1986
CONSERVATION DIVISION
Wichita, Kansas

INVOICED / Reserve this plugging.

DATE JUN 3 1986
INV. NO. 14037

Signed *Jack R. Smith*
(TECHNICIAN)