

2 060023

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077 20.943 -00-00  
CNE  
NW 1/4 SEC. 36, T. 32S, R. 8W E

660 FEET FROM NS SECTION LINE

1980 FEET FROM WE SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5313

LEASE NAME MATHIS WELL # B-2

OPERATOR F&M Oil Co  
NAME & ADDRESS 422 Union Ctr.  
Wichita, KS

COUNTY HARPER

WELL TOTAL DEPTH 4906 FEET \$159.45

CONDUCTOR PIPE: SIZE — FEET —

SURFACE CASING: SIZE 8 5/4 FEET 252'

ABANDONED OIL WELL — GAS WELL — INPUT WELL — SWD WELL — D&A X

OTHER WELL AS HEREINAFTER INDICATED —

PLUGGING CONTRACTOR Mustang Drilling LICENSE NUMBER 5652

ADDRESS P.O. Drawer 1609 Great Bend KS 67530

COMPANY TO PLUG AT: HOUR: — DAY: 23 MONTH: 10 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM MUSTANG DRILL.

(COMPANY NAME) ABOVE (PHONE) —

WERE: Fill Hole with Mud

35 SXS @ 800' Displaced with Drill Mud

35 SXS @ 300'

25 SXS on top W-R Plug @ 60'

10 SXS in Rat hole

PLUGGING PROPOSAL RECEIVED BY R. Wilson  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL — PART — NONE X

OPERATIONS COMPLETED: HOUR: 7:20 AM DAY: 23 MONTH: 10 YEAR: 1983

ACTUAL PLUGGING REPORT Filled hole with Drill mud & Sun

Cementing pumped 35 SXS 60-40 Poz 3 7/8 CC & 2 5/8 CC @ 800'  
Displaced with Drill mud.

35 SXS 60-40 Poz 3 7/8 CC & 2 5/8 CC @ 300'

Pushed Plug & Circ. 25 SXS @ 60' to surface

Then P.P. Circ. 10 SXS Rat hole.

REMARKS: Pumped 5 Barrels Fresh Water Ahead Each Plug

Sun Ticket # 13794

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED R. Wilson Dist II  
(TECHNICIAN)

INVOICED

DATE 11-7-83

INV. NO. 5999-6

OCT 26 1983

FORM CP-2/3  
REV. 6-83