

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-077-20329-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003 *4/91*

ADDRESS 110 South Main Suite 500 Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Lario Slagell WELL NO. 1 WELL LOCATION C-NW-NE COUNTY Harper

SEC. 26 TWP. 32 RGE. 8W (E) or (W) TOTAL DEPTH 4437' PLUG BACK TD 4437

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 223' CEMENTED WITH 225 SACKS

CASING SIZE 5-1/2" SET AT 4422' CEMENTED WITH 200 SACKS

PERFORATED AT 4422'-4437' Open Hole

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ +-4372' (keep within 100' base of 5 1/2" casing).

Cap with 2 sacks of cement. Approximate top of cement 3222'. Shoot according to

stretch. Pull 5 1/2" to 1270' spot 25 sacks of cement. See back side

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Will Notify KCC

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429 *4/91*

ADDRESS Attica, KS PHONE # (316) 254-7204

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Daryl Hanson*
(Operator or Agent)

DATE: 6-8-90

2

Pull 5½" to 820' spot 25 sacks of cement. Pull 5½" to 273' - circulate cement to surface. Pull remaining 5½" casing from hole. Top off 8-5/8" with cement. Cut off 8-5/8" surface pipe 3' below ground level.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 20, 1990

McCoy Petroleum Corporation
110 South Main, Suite 500
Wichita, KS 67202

Lario Slagell #1
C NW NE 26-32-08W
Harper County, KS
API No. 15-077-20,329

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #2, 202 W. First St., #304
Wichita, KS 67202
(316) 263 - 3238