

TYPE

AFFIDAVIT OF COMPLETION FORM

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # N/A EXPIRATION DATE N/A

OPERATOR TXO PRODUCTION CORP. API NO. 15-077-20810-00-00

ADDRESS 200 W. Douglas, Ste. 300 COUNTY Harper

Wichita, KS 67202 FIELD Sullivan

\*\* CONTACT PERSON Harold R. Trapp PROD. FORMATION Stalnaker

PHONE 265-9441

PURCHASER Delhi LEASE Antrim

ADDRESS 2150 Fidelity Union Tower WELL NO. "A" #2

Dallas, TX 75201 WELL LOCATION C NW NW

DRILLING FWA, Rig #32 660 Ft. from North Line and

CONTRACTOR P.O. Box 970 660 Ft. from West Line of

ADDRESS Yukon, OK 73099 the NW (Qtr.) SEC 30 TWP 32S RGE 8W.

PLUGGING N/A WELL PLAT (Office Use Only)

CONTRACTOR N/A

ADDRESS

TOTAL DEPTH 4050 PBD 4037

SPUD DATE 5-30-82 DATE COMPLETED 6-16-82

ELEV: GR 1441 DF N/A KB 1452

DRILLED WITH (CANN) (ROTARY) (TOOL) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING

USED TO DISPOSE OF WATER FROM THIS LEASE 110,924-C (18 741)

Amount of surface pipe set and cemented @ 253' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED BY THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RECEIVED  
CORPORATION COMMISSION

JUL 30 1982

CONSERVATION DIVISION  
Wichita, Kansas

A F F I D A V I T

Harold R. Trapp, being of lawful age, hereby certifies


that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Harold R. Trapp (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 29th day of July

19 82.



Bonnie J. Holcomb (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12-23-85

\*\* The person who can be reached by phone regarding any questions concerning this information.

OPERATOR TXO PRODUCTION CORP LEASE Antrim "A" #2 SEC. 30 TWP 32S RGE. 8W

**FILL IN WELL LOG AS REQUIRED:**

FORMATION DESCRIPTION, CONTENTS, ETC.			TOP	BOTTOM	NAME	DEPTH
<small>Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time test open, flowing and shut-in pressures, and recoveries.</small>					LOG TOPS	
					Topeka	3224 -1772
					Heebner	3376 -1924
					Douglas Grp.	3414 -1962
					Iatan	3664 -2212
					Stalnaker	3668 -2216
					Kansas City	3945 -2493
					RTD	4050
					LTD	4033
					Ran O.H. Logs	
		No DSTs.				

**Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Seals	Type and percent additives
Surface	12 1/4	8-5/8"	24#	253'		150 sxs	1 lbite + 150 Class "A"
Production		4-1/2"		4049'		25 Scavenger	+ 200 RFC w/W. additives

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Seals cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	82 holes	Stal.	3708-16, 3668-3700

**TUBING RECORD**

Size	Setting depth	Packer set at
2-3/8"	3640	3607

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
N/A	N/A

Date of first production 7-27-82	Producing method (flowing, pumping, gas lift, etc.) flowing	Gravity N/A
RATE OF PRODUCTION PER 24 HOURS ON 16.70 BO	Gas 1725 MCFD	Water N/A % 0
Disposition of gas (vented, used on lease or sold) Sold	Perforations 3708-16, 3668-3700	