

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OKWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR TXO Production Corp. API NO. 15-077-20,703-00-00

ADDRESS 200 W. Douglas, Ste. 300, Wichita, KS COUNTY Harper

FIELD Sullivan

**CONTACT PERSON Harold R. Trapp LEASE Robinson

PHONE 265-9441

PURCHASER Shut-in WELL NO. #1 Robinson "G"

ADDRESS N/A WELL LOCATION

1650 Ft. from South Line and

2310 Ft. from East Line of

the 21 SEC. 32S TWP. 8W RGE.

DRILLING CONTRACTOR Freeman, Rig #1

ADDRESS 251 N. Water, Wichita, Ks. 67202

WELL PLAT
(Quarter) or (Full) Section - Please indicate.

PLUGGING CONTRACTOR N/A

ADDRESS N/A

TOTAL DEPTH 3900' PBTD 3858'

SPUD DATE 7-15-81 DATE COMPLETED SI 8-11-81

ELEV: GR 1414 DF N/A KB 1426

KCC
KGS

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(DRILL)~~ TOOLS (New) / ~~(Used)~~ casing.

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface		8-5/8"	24#	267'	Class "H"	250	3% CaCl & 2% c
Production			10.5#	3899'	Scavenger Class "H"	25 200	500 gals mud f 40 bbls 2% KC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF (9 holes)		2680-84'
TUBING RECORD			2 JSPF (21 holes)		3666-76'
			2 JSPF (21 holes)		3634-44'
Size	Setting depth	Packer set at			
2-3/8"	3990	3559			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Treated w/2500 gals 15% HCl w/c/a-sta & FE. 55 ball sealers	Those above.

TEST DATE: _____ PRODUCTION FORMATION: Stalnaker

Date of first production Shut-in 8-11-81 Producing method (flowing, pumping, gas lift, etc.) shut-in gas A.P.I. Gravity N/A

RATE OF PRODUCTION PER 24 HOURS N/A Oil N/A Gas 1018 MCFD Water mist Cost/bbl ratio N/A CFPB

Description of gas treated, used or sold: Shut-in Producing intervals: 3680-84, 3666-76, 3634-44

** The person who can be reached by phone regarding any questions concerning this information.

A witnessed initial test by the Commission is required if the well produces more than 15 BBL per day located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unknown Depth Unknown
 Estimated height of cement behind pipe Circulated to surface

WELL LOG

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS SUM, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOG TOPS</u>				
Heebner	3343	-1917		
Iatan	3626	-2200		
Stalnaker	3632	-2206		
RTD	3900			
LTD	3884			
PBD	3858			
DST #1, 3622-34' (Stalnaker), w/results as follows:				
IFP/30": 104-104#, good blow				
ISIP/60": 768#				
FFP/45": 92-81#, GTS in 25"				
Gauged 12.7 incr. to 17.1 MCFD				
FSIP/90": 1049#				
Rec: 75' GCM				
DST #2, 3622-54' (Stalnaker), misrun.				
Ran O.H. Logs				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:


THAT HE IS District Geologist FOR TXO PRODUCTION CORP. OPERATOR OF THE Robinson "G" LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. "G" #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF October 1981, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold R. Trapp

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th DAY OF November 1981

Gayle E. McFadden
 NOTARY PUBLIC



MY COMMISSION EXPIRES: _____