

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-007-20.199-00-02 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Woolsey Petroleum Corp. OPERATOR'S LICENSE NO. 5506

ADDRESS 107 N Market #600 Wichita, KS 67202 PHONE # (316) 267-4379

LEASE (FARM) Lemon WELL NO. 1-C WELL LOCATION NE NW COUNTY BA

SEC. 17 TWP. 30 RGE. 13 (E) or (W) TOTAL DEPTH 4780' PLUG BACK TD 4680'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 309' CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2" SET AT 4778' CEMENTED WITH 165 SACKS

PERFORATED AT 4606' to 4630' - 4410' to 4420' - 4431' to 4441'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4360' & place 4 sax cement w/ bailer,

pump 300# hulls, 10 sax gel, 50 sax cement, 10 sax gel, 100# hulls, 8 5/8"

plug & 125 sax cement down 8 5/8" casing. Use 40/60 poz + 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9-4-92 1:00 pm

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE # (316) 478-2890

ADDRESS Route #1 Box 16A-3 Milton, KS 67106

PLUGGING CONTRACTOR Pratt Well Service LICENSE NO. N/A

ADDRESS Box 847 Pratt, KS 67124 PHONE # (316) 672-2531

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Carl W. Durr  
(Operator or Agent)

DATE: 9-9-92