

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER. 15-077-20,615-00-00

LEASE NAME Antrim

WELL NUMBER #3

1320' Ft. from S Section Line

1320' Ft. from E Section Line

SEC. 30 TWP. 32S RGE. 8 XXXX (W)

COUNTY Harper

Date Well Completed 9-19-80

Plugging Commenced 4-28-87

Plugging Completed 4-29-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202

PHONE#(316) 269-7600 OPERATORS LICENSE NO. 5171

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? Unknown

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	6 jts	
				2-7/8"	124 jts	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 1/2 sx hulls + 10 sxs 60/40 poz w/ 2% gel into perfs. Squeezed to 1500 psig. RU Electra, perf 2-7/8" csg from 382-85' w/ 2 JSPF. Broke circ w/ fresh wtr & started cementing. Cmt squeezed to 1500 psig. w/ no cmt in annulus. TH w/ 1-1-2" tbg circulating clean. Hit hard object @ 350', worked down to 396', est circ. Cmt w/ 150 sxs 60/40 poz w/ 2% gel, good circ. thruout. Cmt did circ  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service License No. 5893

Address Box 847, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey S. Childs (Employee of Operator) or (~~Inspector~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeffrey S. Childs

(Address) Jeffrey S. Childs  
155 N. Mkt. Ste 1000, Wichita, KS. 67202

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 87

Connie F. Koehler  
Notary Public

My Commission Expires: July 10, 1988

Connie F. Koehler  
NOTARY PUBLIC  
State of Kansas  
APPT. EXPIRES 7/10/88

RECEIVED, 19 87  
MAY 12 1987  
5-12-87  
CONSERVATION DIVISION  
Wichita, Kansas CP-4  
Revised 07-86