

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER. 15-077-20,449-00-0

LEASE NAME Antrim

WELL NUMBER #1

1320' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 30 TWP. 32S RGE. 8 XXXX (W)

COUNTY Harper

Date Well Completed 4-8-78

Plugging Commenced 4-28-87

Plugging Completed 4-29-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO PRODUCTION CORP.

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202

PHONE# (316) 269-7600 OPERATORS LICENSE NO. 5171

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? Unknown

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4851'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	285.30	
				4-1/2"	4556'	69 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH w/ dump bailer, top of sand @ 3340'. Dump 4 sxs cmt on top of sand. Pulled stretch csg, free point @ ± 2800'. RU Electra, shot csg off @ 2817'. POOH & LD 69 jts, 4-1/2", 10.5# csg. Plug surface csg w/ 3 sxs hulls, 15 sxs gel, 150 sxs 60/40 poz w/ 2% gel. Max Pressure: 800 psig. ISTP=600 psig. Well plugged on 4-29-87.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address Box 847, Pratt, KS. 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey S. Childs (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeffrey S. Childs

(Address) Jeffrey S. Childs
155 N. Market, Suite 1000, Wichita, KS. 67202

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1987

Connie F. Koehler
Notary Public

My Commission Expires: July 10, 1988

Connie F. Koehler
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES

RECEIVED
STATE CORPORATION COMMISSION
5-12-87
MAY 12 1987 Form CP-4
Revised 07-86
CONSERVATION DIVISION
Wichita, Kansas