

15-077-10189-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas


Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 30 Twp. 32 Rge. 8 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines G E/2 E/2 SW  
Lease Owner Clinton Oil Company  
Lease Name Heacock Ely Well No.  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 5/6/71 19  
Plugging completed 5/10/71 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 3765 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8		none
				4"	3764'	2990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3741', ran sand to 3685' and dumped 4 sacks of cement. Loaded hole, took head apart, had slip on collar welded on. Rigged up over 4", removed slips, laid floor out and removed head and put stripper head on. Rigged back up, shot pipe at 3000', pulled 22 joints and well blew in. Globe pumped 31 sacks of weight mud and 18 sacks gel, pulled 23 more joints and well was dead. Pulled 49 joints. Set rock bridge 265 to 245' and dumped 4 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

Subscribed and Sworn to before me this 13 day of May, 1971  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires Feb. 15, 1975

Margaret Melcher  
Notary Public.

# WELL LOG

COMPANY Continental Oil Company

SEC. 30 T. 32S R. 8W

FARM Heacock & Ely GU NO. 1


LOC. C E/2 E/2 SW

TOTAL DEPTH 3765'

COUNTY Harper

COMM. 8-28-63

COMP. 9-6-63



CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 277.49' KB w/175 sx

4 1/2" @ 3765' w/150 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 15' Sand
- 145' Red Bed and Shale
- 180' Red Rock
- 285' Red Bed
- 725' Red Bed and Shale
- 905' Shale and Shells
- 930' Anhydrite
- 1430' Shale and Shells
- 1810' Lime
- 1926' Shale and Lime
- 2070' Shale
- 2450' Shale and Lime
- 2590' Shale
- 2779' Shale and Lime
- 2859' Lime and Shale
- 2970' Shale and Lime
- 3360' Lime and Shale
- 3670' Shale and Lime
- 3698' Shale
- 3765' Stalneckers Sand
- 3765' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

State Corp. Comm.  
Kansas Geological Society  
File

State of Kansas }  
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Heacock & Ely GU #1 well.

*Sam N. Stephens*

Subscribed and sworn to before me this 11th day of September 1963

My Commission Expires: April 14th, 1967

*Arthur J. [Signature]*  
NOTARY PUBLIC