

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,329-00-00

LEASE NAME Lario Slagell

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 32 SRGE. 8 or (W)

COUNTY Harper

Date Well Completed 10-75

Plugging Commenced 6-6-90

Plugging Completed 6-7-90

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE#(316) 265-9697 OPERATORS LICENS. NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well loc. attached?

Producing Formation Mississippian Depth to Top 4422' Bottom 4437' T.D. 4437'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	223	None
				5-1/2"	4422	2565'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4372'. Place 2 sacks cement on top of plug with Dump Bailer. Load casing with water. Cut off casing @ 2565'. Circulate hole. Set cement plugs with Halliburton Pump Truck using 40-60 Pozmix, 6% gel, as follows: Bottom of 1st plug @ 1273' w/25 sks, 2nd plug @ 819' w/25 sks, top plug @ 334' w/100 sks to surface. Cut off surface casing 5' below GL.

(If additional description is necessary, use BACK of this form.)
Plugging complete 6-7-90.

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.


(Signature) John Roger McCoy
(Address) 110 S. Main, Suite 500
Wichita, Kansas 67202

STATE OF KANSAS

10-17-90

OCT 17 1990

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1990



Deborah Ann Paulus
Notary Public

January 8, 1992