

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,899-00-00

LEASE NAME Slagell

WELL NUMBER 1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 26 TWP. 32S RGE. 8 or (W)

COUNTY Harper

Date Well Completed 5-83

Plugging Commenced 6-5-90

Plugging Completed 6-6-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Stalnaker Sand Depth to Top 3646 Bottom 3660 T.D. 3952'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	262'	None
				4-1/2"	3947'	2113'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Set CIBP @ 3600'. Place 2 sacks cement on top of CIBP with pump bailer. Load casing with water. Cut off casing @ 2113'. Circulate hole. Set cement plugs with Halliburton Pump Truck using 40-60 Pozmix, 6% gel, as follows: Bottom of 1st Plug @ 1290' w/25sacks 2nd plug @ 797' with 25 sacks, top plug @ 323' w/90 sacks, cement to surface. Cut off surface casing 5' below GL. Plugging Complete 6-5-90.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas

JUN 28 1990

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1990



Deborah Ann Paulus
Notary Public

January 8, 1992