

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Robinson Oil Company

ADDRESS 300 W. Souglas Suite 420 Wichita, KS 67202

PHONE#(316) 262-6734 OPERATORS LICENSE NO. 5038

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4694'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	254'	none
				4 1/2"	4691'	2962'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4600' ran 4 sacks cement. Shotpipe @3510', 3309', 3109', 2962'. Pulled to 1000' pumped 35 sacks cement, pulled to 700' pumped 35 sacks cement, pulled to 300' circulated cement.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*


RECEIVED (Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 20 day of Nov., 19 90

NOV 21 1990

Jane Thompson
Notary Public

My Commission Expires:



WELL LOG
Dalrymple A 1-26
NE NE 26-33S-8W
Harper County, Kansas

Name of Operator: Sweetman Drilling, Inc. & Robinson Oil Co.
1632 Vickers KSB & T Bldg.
Wichita, Kansas 67202


Date Completed: July 15, 1973

<u>FROM</u>	<u>TO</u>	
0	725	Red bed and shale
725	1350	Shale
1350	3856	Lime and shale
3856	3940	Stal. Sand
3940	4071	Lime and shale
4071	4624	Lime
4624	4693	Miss. Lime
4693		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.



Gary L. Hawk

Subscribed and sworn before me this 17th day of July, 1973.



Notary Public Barton County

My Commission Expires 7-10-77

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1973

CONSERVATION DIVISION
Wichita Kansas