

API NUMBER 15-007-19078-00-00

LEASE NAME Binning

WELL NUMBER 1

         Ft. from S Section Lin

         Ft. from E Section Lin

SEC. 26 TWP. 36 RGE. 13 ~~XX~~ or (W)

COUNTY Barber

Date Well Completed 11-24-63

Plugging Commenced 9-3-92

Plugging Completed 12:45 PM

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bowers Drilling Co. Inc.

ADDRESS P.O. Box 241, Medicine Lodge, Ks 67104

PHONE# 816 886-5520 OPERATORS LICENSE NO. 5435

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-3-92 (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?         

Producing Formation          Depth to Top 3569 Bottom 3576 T.D. 3930

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	280	0
				4 1/2	3930	2415

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from          feet to          feet each:

Bottom plug: Sanded to 3500 & bailed 4 sx cement.

Top plug: Pumped 3 lbs Hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs Hulls, Wiper plug, 100 sx cement (60/40 6% gel) Max pressure of 900 lbs & shut in of 300 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowers Drilling Co, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) of Wichita, Kansas

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 4 day of September, 19 92



Anna K. Burke  
 Notary Public

My Commission Expires: 4-30-96

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 8 1992

CONSERVATION DIVISION  
 Wichita, Kansas