

STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County. Sec. 26 Twp. 32S Rge. 13 (E7) (W)

Location as "NE/CNW/SW" or footage from lines C E/2 SW NW

Lease Owner Bowers Drilling Company, Inc.

Lease Name Binning "A" Well No. 1

Office Address 416 Union Center Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-19-64 19

Application for plugging filed 1-23-64 19

Application for plugging approved 1-19-64 19

Plugging commenced 1-19-64 19


Plugging completed 1-19-64 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8-5/8", PUT IN 313.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300'
Set first plug at 300' with 1 sack hulls and 25 sacks cement
Filled with heavy mud to 40'
Set second plug at 40' with 1/2 sack hulls, 15 sacks cement, 2 sacks in rat hole

RECEIVED STATE CORPORATION COMMISSION

JAN 27 1964

CONSERVATION DIVISION Wichita, Kansas

Name of Plugging Contractor Bowers Drilling Company, Inc. Address 416 Union Center Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss. Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers 416 Union Center, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1964

My commission expires May 1, 1966 Notary Public.



WELL LOG

COMPANY:	Bowers Drilling Company, Inc.
CONTRACTOR:	Bowers Drilling Company, Inc.
FARM:	Binning "A" #1
LOCATION:	C E/2 SW NW Section 26-32S-13W Barber County, Kansas
COMMENCED:	January 7, 1964
COMPLETED:	January 19, 1964
ELEVATION:	1656 Kelly Bushing

0 - 315	Shale	Ran 313' of 8-5/8" casing
315 - 1797	Redbed and shale	
1797 - 2191	Lime and shale	
2191 - 2445	Lime	Ran 313' of 8-5/8" casing with 225 sacks
2445 - 2621	Lime and shale	
2621 - 2758	Lime	
2758 - 3600	Lime and shale	
3600 - 3749	Elgin sand - lime and shale	
3749 - 3999	Lime and shale	
3999 - 4135	Lime	
4135 - 4206	Lime and shale	
4206 - 4452	Lime	
4452 - 4475	Chalky lime and shale	
4475	T. D.	

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1964

CONSERVATION DIVISION
Wichita, Kansas

LOG TOPS:

Elgin Sand	3594	Lansing	3902
Heebner Shale	3716	Base Kansas City	4262
Upper Douglas Sand	3792	Mississippian Chert	4409
		Mississippian Limestone	4421

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Binning "A" #1 located C E/2 SW NW Section 26-32S-13W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 23rd day of January, 1964.

Donna F. Miller
Donna F. Miller, Notary Public

My commission expires May 1, 1966