

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-007-21267-00-0

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Lonker

WELL NUMBER #1

SPOT LOCATION E/2-NE-SE

SEC. 24 TWP 325 RGE. 13 (E) OR (W)

COUNTY Barber

DATE WELL COMPLETED 9/21/81

1:50  
PLUGGING COMMENCED 9/22/84

PLUGGING COMPLETED 10/1/84

LEASE OPERATOR Graves Drilling Co.

ADDRESS 910 Union Center, Wichita, KS 67202

PHONE #(316) 265-7233 OPERATORS LICENSE NO. 5422

CHARACTER OF WELL oil  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, KS

IS ACC-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 4477

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

FORMATION.	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	202	None
				4 1/2	4476	3600

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plug back - 4551

Sand from 4551 to 4375 - 4 sack cement from 4375 to 4345, 3 hull, 10 jell, 50 cement  
10 sx jell, 1sx hull, 100sx cement - 60-40 POZ - 2% jell, 3% CC

Motz and Morgenstern on location

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Clarke Corp. LICENSE No. 5105

ADDRESS 107 W. Fowler, Medicine Lodge, KS 67104

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, SS.

(EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Ch. P. Morgenstern

(ADDRESS) \_\_\_\_\_

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3 DAY OF October, 1984

Pamela Ricke

MY COMMISSION EXPIRES: 10-11-87

PAMELA RICKE  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. \_\_\_\_\_

NOTARY PUBLIC  
RECEIVED  
STATE OF KANSAS  
10-16-84  
OCT 16 1984

FORM CP-4  
REVISED 06-83

CONSTABLE OF DISTRICT

# Graves DRILLING CO. INC.

TEL. 316-265-7233

910 UNION CENTER

WICHITA, KANSAS 67202

## DRILLING REPORT

RECEIVED  
OCT 5 1984  
BUREAU OF  
TRAFFIC ENGINEERING

Re: TXO Farmout  
Lonker No. 1  
100' N of E/2 NE SE  
Section 24-32S-13W  
Barber County, Kansas  
Elevation: 1597 G.L.  
1603 K.B.

- 9-21-81 Moving in Graves' rotary tools, rig up, spud and run surface. Spud at 2:20 P.M. Cut 208' of 12 $\frac{1}{4}$ " hole & ran a straight hole test off 3/4". Ran 5 Jts. of new 8-5/8" 23#, tallied 196.06' set @ 208' with 175 sacks common cement, 2% Gel, 3% CC. Plug to 190' at 6:30 P.M.
- 9-22-81 Drilling @ 760' at 6:00 A.M.
- 9-23-81 Drilling @ 1840' at 9:00 A.M.
- 9-24-81 Drilling @ 2781' at 9:00 A.M.
- 9-25-81 Drilling @ 3188' at 6:00 A.M.
- 9-26-81 Drilling @ 3630' at 9:00 A.M.
- 9-27-81 Drilling @ 4200' at 8:00 A.M.
- 9-28-81 Logging @ 4476' RTD @ 7:00 A.M. Will run new 4 $\frac{1}{2}$ " 10.5# casing set at 2' off bottom. Ran 114 Jts. new 4 $\frac{1}{2}$ " 10.5# casing, tallied 4477.44' set @ 4475' with 75 sacks cement. Plug to 4460' at 10:45 P.M.

### Log Tops:

Base of Wellington	1923 (- 315)
Winfield	1991 (- 383)
Towanda	2062 (- 454)
Council Grove	2472 (- 864)
Neva	2531 (- 923)
Indian Cave Shale	2746 (-1138)
Wabaunsee	2800 (-1192)
Tarkio	2944 (-1366)
Elgin Shale	3526 (-1918)
Heebner	3686 (-1978)
Lansing	3860 (-2252)
Stark	4230 (-2622)
Mississippi	4393 (-2785)
Mississippi Porosity	4413 (-2805)
LTD	4480 (-2872)

### Sample Tops:

Cottonwood Lime	2472 (- 864)
Indian Cave Shale	2748 (-1140)
Wabaunsee Lime	2801 (-1193)
Tarkio Lime	2941 (-1333)
Elgin Shale	3516 (-1908)
Heebner	3688 (-2080)
Douglas Shale	3757 (-2149)
Lansing	3861 (-2253)
RTD	4476 (-2868)

RECEIVED  
STATE ENGINEERING BOARD

OCT 16 1984

CHIEF ENGINEER  
WICHITA, KANSAS

459  
452

452