

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-2146-0000
007-2146-00-00
API NUMBER 15-0072-1-460

LEASE NAME Lonker
WELL NUMBER #3
SPOT LOCATION NE SW NE
SEC. 24 TWP. 32 RGE. 13 (E) or (W)
COUNTY Barber
Date Well Completed 6/23/82
Plugging Commenced 6/1/84
Plugging Completed 6/7/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graves Drilling Company
ADDRESS 910 Union Center, Wichita, Kansas 67202
PHONE # (316) 265-7233 OPERATORS LICENSE NO. 5428
Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? Dodge City
Is ACO-1 filed? _____ If not, is well log attached? yes

Producing formation Mississippi Depth to top 4450 bottom T.D. 4450
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	230	none
1257				4 1/2	4480	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. plug back at 4438 sand from 4438 to 4324 4 sacks cement with dump bailer from 4324 to 4290 ripped pipe at 2800 Buie pumps in 2 sacks hulls 15 sacks jell 50 sacks cement 1 sacks hull 100 sacks cement 60/40 POZ 2% jell 3%CC

Motz and Morgenstern on locat

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105
Address Box 187, Medicine Lodge, Kansas 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo R. Morgenstern (employee of operator) or (operator) of above-described well being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JUN 11 1984

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Elmo R. Morgenstern
(Address) Medicine Lodge, Ks.

SUBSCRIBED AND SWORN TO before me this 11 day of June, 19 84

Fessie Hamilton
Notary Public

My Commission expires: April 4, 1986