


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 35 Twp. 33 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
SE NW SW

Lease Owner Andover Oil Co.
Lease Name Robert E. Thompson #1 Well No. _____
Office Address Tulsa, Oklahoma
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/7/79 _____ 19____
Plugging completed 2/10/79 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4800
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	189	none
				1 1/2"	4800	3832

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Squeezed bottom hole with 35 sacks cement, pumped plug to 4473'. Top of cement at 4582'.
Loaded 1 1/2" casing with 25 bbls. salt water. Shot pipe at 4240', 4010', 3830'. Worked
pipe loose and pulled 100 joints. Squeezed hole with 5sacks hulls, 20 sacks gel, released
plug and displaced with 100 sacks 60/40 pozmix, 2% gel and 3% cc.

PLUGGING COMPLETE.

RECORDED
STATE CORPORATION COMMISSION
FEB 16 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 79



Margaret Melcher
Notary Public.

My commission expires _____

DRILLEPS' LOG

SANDS DRILLING COMPANY
 No. 1 Robert E. Thompson
 SE NW SW, Sec. 35-33S-13W
 Barber County, Kansas

Commenced: 3-19-76
 Completed: 3-28-76

Surface Casing: 189' of
 8-5/8" cemented w/180 sx
 common cement, 3% cc.
 3-19-76

FORMATIONDEPTH

Surface Hole	0 - 196
Red Bed-Shale	196 - 930
Shale	930 - 1689
Shale & Shells	1689 - 2010
Shale	2010 - 2165
Shale & Lime	2165 - 2450
Lime & Shale	2450 - 2760
Shale & Lime	2760 - 3030
Lime & Shale	3030 - 3330
Shale & Lime	3330 - 3885
Lime & Shale	3885 - 4185
Shale	4185 - 4375
Lime	4375 - 4640
Shale & Lime	4640 - 4670
Lime & Shale	4670 - 4755
Lime	4755 - 4800 RTD

RECEIVED
 STATE CORPORATION COMMISSION

OCT 25 1978
 10-25-78
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 1st day of April 1976.

Ella Pries
 Ella Pries, Notary Public

