

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Barber County, Sec. 26 Twp. 30S Rge. (E) 13(W)

Location as "NE/CNW%SW%" or footage from lines C NE SE

Lease Owner Texas Energies, Inc.

Lease Name Smith Well No. 1-A

Office Address 816 Bank of the Southwest Bldg., Amarillo, Tex.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 25, 19 68

Application for plugging filed November 25, 19 68

Application for plugging approved November 25, 19 68


Plugging commenced November 25, 19 68

Plugging completed November 25, 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (R. J. Warren of Pratt)



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4530 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	330'	8-5/8"	11/13/68	-----
	Casing					

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 250 Feet;  
1/2 sax Hulls, Plug and 25 sacks Cement  
thru to Drill Pipe; Mud to 40 Feet;  
1/2 sax Hulls, Plug bridged with Kelly  
and 10 sax Cement to Base of Cellar;  
2 sax Cement in Rat Hole. Job Completed  
@ 6:00 P.M. on 11/25/68.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.  
Address 500 Bitting Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) T. M. McCaul, Jr.

500 Bitting Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of December 19 68

November 26, 1970.

Louise K. Whitted - Notary Public.



DRILLERS LOG

SMITH NO. 1-A

SURFACE CASING: 8-5/8" @ 330' w/275 sax cement  
TOTAL DEPTH: 4530'

OPERATOR: Texas Energies, Inc.  
CONTRACTOR: Sage Drilling Co., Inc.  
COMMENCED: November 13, 1968  
COMPLETED: November 26, 1968

DESCRIPTION: C NE SE  
Sec. 26-30S-13W  
Barber County, Kansas  
ELEVATION: 1894KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	332	
Red Bed & Shale	332	1185	
Shale & Lime	1185	1995	
Lime & Shale	1995	2400	
Shale & Lime	2400	2610	
Lime & Shale	2610	4105	
Lime	4105	4513	
Lime, Shale & Chert	4513	4530	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.  
T. M. McCaul, Jr.



Subscribed and sworn to before me this 2nd day of December, 1968.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.