


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 1 Twp. 30S Rge. 13W E4W  
Location as "NE/CNW/SW" or footage from lines  
C-SW SW SW

Lease Owner Carl Todd  
Lease Name Levens Well No. 1  
Office Address 1117 West River Blvd., Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed June 22, 1980  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced June 22, 1980  
Plugging completed June 22, 1980  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen  
Producing formation Depth to top Bottom Total Depth of Well 2,835  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 2,835 ft. (rotary total depth) to 210 ft. Set plug at 210 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 210 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas 67202

STATE CORPORATION COMMISSION  
RECEIVED JUL 8 1980  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Employed by owner) or owner or operator

I, the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God

(Signature) Dean Britting  
251 N. Water #10, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 1980

Elsie Willison - Notary Public.

commission expires July 3, 1982

KANSAS DRILLERS LOG

COMPANY Carl Todd  
 FARM Levens NO. 1

SEC. 1 T. 30S R. 13W  
 LOC. C-SW SW SW

COUNTY Barber

ROTARY TOTAL DEPTH 2,835'  
 COMM. June 17, 1980 COMP. June 22, 1980  
 CONTRACTOR H-30, INC. (Rig #11)  
 ISSUED July 3, 1980

CASING

10 3/4" Set at 205' cemented w/125 sxs cement  
 8 5/8"  
 5 1/2"  
 4 1/2"

ELEVATION 1,821' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand, Shale and Red Bed	215'
Shale	1,990'
Shale and Lime	2,425'
Lime and Shale	2,620'
Lime	2,835'
Rotary Total Depth	2,835'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
 Dean Britting

State of Kansas )  
 ) ss:  
 County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of July, 1980.

*Elsie Willison*  
 Elsie Willison - Notary Public

My Commission Expires:  
 July 25, 1982

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL - 8 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas