

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barber County, Sec. 15 Twp. 30 Rge. (E) 12 (W)

Location as "NE/CNW&SW" or footage from lines. C/SW NW
Lease Owner Lawrence O. Tenk
Lease Name House Well No. 2
Office Address P. O. Box 294, Ottawa, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 16 1966
Application for plugging filed May 16 1966
Application for plugging approved May 16 1966
Plugging commenced May 16 1966
Plugging completed May 16 1966
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4591 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	405'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 300' with 25 sacks of cement and mud to 40'; plugged with 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 8:00 P. M. May 16, 1966.

RECEIVED
STATE CORPORATION COMMISSION

JUN -1 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employer or owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of May, 1966

My commission expires December 14, 1969

Elaine H. Taylor
Elaine H. Taylor Notary Public

D R I L L E R S L O G

#2 House

CASING RECORD: 398.55' of used 8-5/8" surface casing.	COMPANY: Lawrence O. Tenk	DESCRIPTION: C/SW NW Section 15-30-12W Barber County, Kansas
TOTAL DEPTH: 4591'	CONTRACTOR: Strata Drilling, Inc.	
	COMMENCED: May 3, 1966	
	COMPLETED: May 16, 1966	
	D. & A.	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	70	Ran 398.55' of used surface casing; set and cemented at 405' with 300 sacks of cement, 2% gel and 3% calcium chloride. Plug down at 11:45 A. M. May 4, 1966.
Red Bed & Shale	70	958	
Shale & Shells	958	1305	
Shale, Shells & Lime	1305	1905	
Shale & Lime	1905	3698	
Lime, Shale & Sand	3698	3774	
Lime & Shale	3774	3924	
Lime	3924	4377	
Shale	4377	4478	
Lime & Shale	4478	4591	
Total Depth 4591'			Ran two drill stem tests.
			Ran Electra log.
			D. & A.
			Plugged hole as follows: Plugged at 300' with 25 sacks of cement and mud to 40'; plugged with 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 8:00 P. M. May 16, 1966.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION

JUN -1 1966

*CONSERVATION DIVISION
CORPORATION COMMISSION

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 18th day of May, 1966.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1969