


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 15 Twp. 30S Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Wilkinson Drilling, Inc.  
Lease Name KUMBERG Well No. 1  
Office Address 805 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 24 19 65  
Application for plugging filed March 24 19 65  
Application for plugging approved March 24 19 65  
Plugging commenced March 24 19 65  
Plugging completed March 24 19 65  
Reason for abandonment of well or producing formation No oil or gas found  
in commercial quantities.

If a producing well is abandoned, date of last production - - 19 65  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4620 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	321.69'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud back to 275', set bridge with hulls and plug, cemented through drill pipe with 25 sacks, mud back to 40', set solid bridge with hulls and plug, capped with 10 sacks cement. Plug down 12:15 p.m. 3-24-65.

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 1965  
4-2-86  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31th day of March, 19 65

My commission expires January 8, 1968

Shirley Keck  
Shirley Keck Notary Public.

ROTARY DRILLING LOG

Operator: Wilkinson Drilling, Inc.  
#1 Kumberg  
C NW SE Sec. 15-30S-12W,  
Barber County, Kansas

Contractor: Rains & Williamson Oil  
Co.  
Commenced: 3-10-65  
Completed: 3-25-65

Remarks: Set 321.69' of 8 5/8"  
with 250 sx GL3 cement.

Formations:

Surface Soil & Clay	35'
Sand	100'
Shale	110'
Shale & Red Bed	830'
Shale & Shells	1760'
Lime & Shale	3170'
Lime	3181'
Lime & Shale	3870'
Lime	4260'
Shale & Lime	4300'
Lime	4425'
Shale & Lime	4505'
Lime	4566'
Lime & Chert	4600'
Lime	4620'
Rotary Total Depth (D&A)	4620'

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 1965

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By Wilson Rains  
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State  
of Kansas, County of Sedgwick, this 29th day of March, 1965.

My Commission Expires:  
July 25, 1968

Judith Caughlin  
Judith Caughlin