

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Barber County. Sec. 15 Twp. 30S Rge. (E) 12 (W)
 Location as "NE/CNW/SW" or footage from lines C/SW SW
 Lease Owner California-Time Petroleum, Inc.
 Lease Name House Well No. 1
 Office Address P. O. Box 8124, Wichita, Kansas 67208
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed January 16 19 67
 Application for plugging filed January 16 19 67
 Application for plugging approved January 16 19 67
 Plugging commenced January 16 19 67
 Plugging completed January 16 19 67
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4470 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	310'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 300' with 2 sacks of dry cement, 1/2 sack of hulls and 23 sacks of cement and mud to 40'; plugged at 40' with 2 sacks of dry cement, 1/2 sack of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole. Plug down at 2:30 A. M. January 16, 1967.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1967

1-24-67

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
 Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
 Jim B. McWilliams (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
 Jim B. McWilliams, Secy-Treas.
 P. O. Box 355, Great Bend, Kansas 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 67

Elaine H. Taylor
 Elaine H. Taylor Notary Public.

My commission expires December 14, 1969

DRILLERS LOG

#1 House

CASING RECORD:
Ran 304.44' of new
8-5/8" surface casing.

COMPANY: California-Time Petroleum, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW SW
Section 15-30S-12W
Barber County, Kansas

TOTAL DEPTH:
4470'

COMMENCED: January 4, 1967
COMPLETED: January 16, 1967

ELEVATION: 1763' DF

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS:</u>
Sand & Gravel	0	90	Ran 304.44' of new 8-5/8" surface casing; set and cemented at 310' with 225 sacks of regular cement. Plug down at 10:45 P. M. January 5, 1967. Cement circulated.
Shale, Sand & Gravel	90	600	
Shale	600	1100	
Shale & Shells	1100	1765	
Shale & Lime	1765	3795	
Lime	3795	4470	

Total Depth 4470'

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1967

CONSERVATION DIVISION
Wichita, Kansas


D. & A.

Plugged hole as follows: Plugged at 300' with 2 sacks of dry cement, 1/2 sack of hulls and 23 sacks of cement and mud to 40'; plugged at 40' with 2 sacks of dry cement, 1/2 sack of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole. Plug down at 2:30 A. M. January 16, 1967.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 17th day of January, 1967.


Elsie H. Taylor, Notary Public

My Commission Expires:
December 14, 1969