


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
809 Bittling Building
Wichita, Kansas

Barber County. Sec. 15 Twp. 30S Rge. (E) 12 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4, NE/4, NW/4,
Lease Owner National Associated Petroleum Co.,
Lease Name Gust Kumberg Well No. 1
Office Address 502 Ritz Bldg. Tulsa, Oklahoma.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 20th 19 51
Application for plugging filed November 20th 19 51
Application for plugging approved November 20th 19 51
Plugging commenced November 20th 19 51
Plugging completed November 20th 19 51
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4763 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	293'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with Heavy Mud to 294 Feet, Set Bridge Plug at 294 Feet, 15 Sacks Cement on Plug, Heavy Mud to 35 Feet, Base of Cellar, 10 Sacks Cement to Bottom of Cellar, Cemented thru Drill Pipe.

FILED
NOV - 7 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to National Associated Petroleum Co.,
Address 502 Ritz Bldg. Tulsa, Oklahoma.

STATE OF Kansas COUNTY OF Sedgwick ss.
R. C. Patton (Drilling Contractor) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.C. Patton
612 Orpheum Bldg. Wichita 2, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of November 19 51
Notary Public.

My commission expires Oct 4th 1952.

PLUGGING
FILE SEC 15T 30 R 12W
BOOK PAGE 118 LINE 31

National Associated Petroleum Co.,
 Gust Kumberg Well #1
 Total Depth 4763 Ft.
 Comm. 9/17/51
 Comp. 10/20/51
 Contractor R. C. Patton Co.,

Sand	107
Red Shale	127
Red Shale, Shale & Shells	235
Shale & Shells	297
Shale	345
Shale, Shells, Anhydrite	1020
Shale & Shells	1400
Shale & Salt	1545
Anhydrite	1640
Shale, Anhydrite	1830
Lime	1960
Lime & Shale	2030
Shale Sandy	2120
Shale Sandy, Shale	2205
Lime & Shale	3125
Lime	3170
Lime & Shale	3685
Lime	3722
Lime & Shale	3767
Sand	3775
Shale Sandy	3789
Lime & Shale	3803
Shale	3805
Lime & Shale	3935
Lime	4065
Lime & Shale	4223
Lime	4216
Lime & Shale	4288
Lime	4354
Lime Cherty	4505
Lime Sandy	4548
Lime & Shale	4575
Shale	4600
Cored	4615
Shale	4666
Lime & Shale	4685
Shale	4691
Lime	4747
Lime Sandy	4759
Sand	4763
Total Depth	4763

Location NE/4, NE/4, NW/4, Section 15-
 T30S-R12W, Barber County, Kansas.
 CASING RECORD.
 8 5/8" Casing at 293 Feet.
 Cemented by 175 Sacks Cement

STATE OF Kansas COUNTY OF Sedgwick SS,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 22nd day of November 1951

PLUGGING
 FILE SEC. 15 T. 30 R. 12W
 BOOK PAGE 118 LINE 31

J. P. Hendrick
 Notary Public.

My Commission Expires Oct 4th, 1952.

NOV 27 1951
 COMMISSIONER OF REVENUE