

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber

County, Sec. 15 Twp. 30S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner K. & E. Drilling, Inc.

Lease Name Kumberg Well No. 1

Office Address 1006 Central Building - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) xxxxxxx dry hole

Date well completed June 12, 1956 - Cleaned out old hole 19

Application for plugging filed June 27, 1956 19

Application for plugging approved June 28, 1956 19

Plugging commenced July 4 19 56

Plugging completed July 7 19 56

Reason for abandonment of well or producing formation commercial quantities of oil not found

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4470 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	514'	None
				5-1/2"	4470'	3925'
				Cement inside pipe not drilled out. Filled to 4438'. Pipe perforated from 4351' to 4371'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 4438' to 4350' and ran 5 sacks of cement. Pulled casing up to 1800' and circulated the hole with 26 sacks of jell mud. Bailed mud to 300', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement to fill to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott

1006 Central Bldg., Wichita, Kansas

(Address)

AND SWORN TO before me this 10th day of July, 19 56

June 25, 1960

Francis M. ... Notary Public.



PLUGGING
FILE SEC 15 T 30 R 12W
BOOK PAGE 75 LINE 9

7-12-56