

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-007-22164-60-01

LEASE NAME McIntire

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER 1
4620 Ft. from N / S Section Line
2310 Ft. from E / W Section Line

LEASE OPERATOR Kestrel Energy Inc.

SEC. 13 TWP. 30N RGE. 12 (E) or (W)

ADDRESS 999 18th St., #2490, Denver, CO 80202

COUNTY Barber

PHONE # 303-295-0344 OPERATOR'S LICENSE NO. _____

Date Well Completed _____

Character of Well Good *Dis*

Plugging Commenced 6-29-2001

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-10-2001

The plugging proposal was approved on 6-29-2001 (date)

by Richard Lacey (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Admire Depth to Top 2784 Bottom 2786 T. D. 3860 *CP 2/3 4728'*

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 262 | None |
| | | | | 5 1/2 | 3917 | 2000 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Lay down rods and tubing, set CIBP at 2490, dump 2sx portland cement with dump bailer, stretch and cut 5 1/2 at 2000,
Lay down 5 1/2, rig down move off. 7/10/01: run 2 3/8 tubing to 700, Allied load hole with jel and spot 50sx cement, pull
Tubing to 290 and spot 50sx cement, pull tubing to 60 and circulate to surface, 60/40, 6% jel, lay down tubing

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kestrel Energy, Inc.

STATE OF Kansas COUNTY of Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.



(Signature) *[Handwritten Signature]*

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 13 day of July,

[Handwritten Signature]
Notary Public

My Commission Expires: November 30, 2002

KANSAS CORPORATION COMMISSION
JUL 18 2001
CONSERVATION DIVISION

OK