

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,984-00-00

LEASE NAME Gibson

WELL NUMBER 1-10

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3585 Ft. from S Section Line

545 Ft. from E Section Line

SEC. 10 TWP. 30 RGE. 12 ~~or~~ (W)

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

COUNTY Barber

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Date Well Completed 3-26-85

Character of Well D&A

Plugging Commenced 3-27-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-27-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	312	8 5/8"	3-16-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 130 sxs Lite, 3% cc, 2% gel as follows: 960'-60 sxs; 330'-40 sxs; 40'-10 sxs with solid bridge, rathole-10 sxs; mousehole-10 sxs. Plug down at 6:30 a.m. on March 27, 1985. State Pluggger was out of the Dodge City, Kansas office.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 3rd day of April, 1985

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Gibson #1-10
 NE SE NE Sec. 10-30S-12W
 Barber County, Kansas
 Commenced: 3-16-85
 Completed: 3-27-85
 API #15-007-21,984
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	130	Sand	Ran 7 joints new, 24#, 8 5/8"
130	320	Red Bed	surface casing. Set at 312' with
320	1400	Red Bed, Shale	200 sxs Common, 2% gel, 3% cc. Job
1400	4800	Lime, Shale	by Sun Cementing. Plug down at
		T.D.	9:45 p.m. on March 16, 1985.

RTD 4800'


Plug well with 130 sxs Lite, 3% cc, gel as follows: 960'-60 sxs; 330'-40 sxs; 40'-10 sxs with solid bridge rathole-10 sxs; mousehole-10 sxs. Plug down at 6:30 a.m. on March 27, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

APR 08 1985