

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

-00-00

API NUMBER 15-007-21,735
LEASE NAME Boyd
WELL NUMBER 1-10
SPOT LOCATION 65' SW of C N/2
SEC. 10 TWP. 30S RGE. 12W or (W)
COUNTY Barber
Date Well Completed 5-27-84
Plugging Commenced 5-27-84
Plugging Completed 5-27-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.
ADDRESS P. O. Box 947
Pratt, KS 67124

PHONE # (316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well DRY
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4810

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	shale	0	305	8-5/8"	302	none
	cemented with 100 sx common,		75 sx light,		2%gel, 3%cc,	
	plug down at 5:45 p.m.	5-14-84	by Halliburton;		cement did circ.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged as follows with 60/40 posmix 2%gel, 3%cc
15 sx in rat hole; 50 sx @ 840'; 40 sx @ 360'; 10 sx @ 40'
w/solid bridge plug; Halliburton; job completed 2:15 a.m. 5-27-84

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Drilling Co., Inc. License No. 5137
Address 200 E. First, Suite 500, Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1984

STATE OF KANSAS COUNTY OF SEDGWICK

Jon T. Williams, Jr. (employee of operator)

(operator) of above-described well, being first duly sworn on oath, say I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 200 East First, Suite 500
Wichita, Kansas 67202



SUBSCRIBED AND SWORN TO before me this 27th day of May, 1984

Geraldine Stewart
Notary Public
Geraldine Stewart

My Commission expires: January 14, 1985