

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 11 Twp. 30S Rge. 12 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines 280' fr N line, 450' fr W line of SW/4

Lease Owner Helmerich & Payne, Inc.

Lease Name Kumberg Well No. 1

Office Address Box 558, Garden City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-21-63 19

Application for plugging filed 5-21-63 19

Application for plugging approved 5-21-63 19

Plugging commenced 5-21-63 19

Plugging completed 5-21-63 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving Pratt, Kansas

Producing formation - Depth to top - Bottom - Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290	8-5/8"	290	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4700' to 220' Heavy Rotary Mud
220' to 145' 1/3 sack hulls & 25 sacks pozmix cement
145' to 40' Heavy Rotary Mud
40' to 4' 1/2 sack hulls & 15 sacks cement
4' to 0 Cellar

PLUGGING COMPLETED 4:00 PM May 21, 1963

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers Drilling Co.

Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.

T. E. Mort (employee of owner) or (Independent) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 558 Garden City, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of May, 1963

Robert N. Boyd
Notary Public.

My commission expires July 1964



SP

DRILLER'S LOG

Well Owner: Helmerich & Payne, Inc.
Farm Name: Sadie Kumborg #1
Commenced: 1-30-63
Completed: 5-21-63
Total Depth: 1700'
Casing: 8-5/8" @ 290 cem.

330' FNL and 150' FWL
Section 11-30S-12W
Barber County, Kansas

Elevation:
Production: Dry

Contractor: Peel Brothers, Inc.

Figures below indicate bottoms of formations:

Sand	0 -	110
Sand and Shale		180
Red Bed		210
Shale and Red Bed		660
Shale and Shells		1750
Lime and Shale		3810
		"
Lime and Chert		1300
Mississippi Lime		1335
Shale		1120
		"
Shale and Lime		1175
Sand		1598
Shale and Sand		1601
		"
Lime		1700
Total Depth		1700

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1963

CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge true and correct.

PEEL BROTHERS, INC.

Wendell C. Peel
Wendell C. Peel
President

SUBSCRIBED AND SWORN to before me this 22nd day of May, 1963.

My commission expires: June 21, 1966

Ethel S. Williamson
Notary Public

NOLIC