


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County. Sec. 11 Twp. 30S Rge. 12W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C W/2 NW SW  
Lease Owner G. N. Rupe  
Lease Name Kumberg "C" Well No. 2  
Office Address P.O. Box 2273, Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry



Locate well correctly on above  
Section Plot

Date Well completed May 24, 1976  
Application for plugging filed October 26, 1977  
Application for plugging approved October 28, 1977  
Plugging commenced November 14, 1977  
Plugging completed November 25, 1977  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production No 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3475  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	None
				4 1/2"	3150'	2026'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back at 2542'  
Sand from 2542' to 2510'  
4 sacks cement from 2510' to 2470'  
Wooden bridge at 273'  
Rock from 273' to 263'  
5 yards of ready mix

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation, 107 West Fowler, Medicine Lodge, Kan. 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.  
RUPE OIL COMPANY, INC. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

G. N. Rupe  
G. N. Rupe, President  
P. O. Box 2273  
Wichita, Kansas (Address) 67201

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1977

My commission expires September 20, 1981

Faye W. Leach  
Faye W. Leach, Notary Public.



CONTRACTOR'S WELL LOG

OPERATOR: Glenn N. Rupe  
CONTRACTOR: Union Drilling Co., Inc.  
WELL NAME: Kumberg C #2  
LOCATION: Approx. NW SW Section 11-30S-12W  
Barber County, Kansas  
COMMENCED: March 7, 1976  
COMPLETED: March 16, 1976

---

0	1400	Shale	8-5/8" casing set at 273 with 250 sacks
1400	1989	Shale & Lime	
1989	2392	Lime and shale	
2392	2586	Lime	
2586	2700	Lime and shale	
2700	2766	Lime	
2766	2899	Lime and shale	
2899	3067	Shale and lime	
3067	3117	Lime and shale	
3117	3191	Lime	
3191	3262	Lime and shale	
3262	3465	Lime	
3465		T. D.	4 1/2" casing set at 3150 with 100 sacks

---


We certify that the above and foregoing is a true and correct copy of the log on the Kumberg C #2, Approx. NW SW Section 11-30S-12W, Barber County, Kansas.

UNION DRILLING CO., INC.

  
R. D. Messinger

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK    )

Subscribed and sworn to before me, a Notary Public in and for the aforesaid county and state as of this 18th day of March, 1976.

  
Donna F. Brown, Notary Public

My commission expires:

July 29, 1978

