

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20684-00-00

LEASE NAME McKaig "A" #2

WELL NUMBER _____

SPOT LOCATION S/2 SE NW
2310' FNL 1980' FW

SEC. 21 TWP. 32 SRGE. 8w (E) or (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 2/13/84

Plugging Completed 2/15/84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 200 W. Douglas, Suite 300, Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. # 5171

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita, Ks

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	256'	none
				4 1/2"	3834'	3060'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.

Bottom was already plugged off, pumped 214 sacks common cement, top of plug at 3580'. Shot pipe at 3327', 3230', & 3060. Pulled 69 joints. Plugged well with 3 hulls, 6 gel, plug, & 100 sacks cement

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1984

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires: _____



Irene Hoover
Notary Public

DRILLERS LOG

OPERATOR: Texas Oil & Gas Corp.
200 West Douglas
Wichita, Kansas 67202

WELL NAME: #2 McKaig 'A'
S/2 SE NW Sec.21-32S-8W
Harper County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 4/30/81

COMPLETED: 5/8/81

RTD: 3850'

SURFACE CASING: 8-5/8" set at 256' with 250 sx

PRODUCTION CASING: 4-1/2" set at 3834' with 135 sx

0' to 261' Surface Hole
261' to 1402' Red Bed
1402' to 1630' Red Bed & Shale
1630' to 2060' Shale
2060' to 3660' Lime & Shale
3660' Stalnaker
3660' to 3850' Lime & Shale
RTD 3850'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the McKaig #2 log for
Texas Oil & Gas.


James C. Remsberg

Subscribed and sworn to me
this 11th day of June, 1981


Mary Lou Taylor, Notary

My commission expires January 17, 1985

