


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Harper County, Sec. 10 Twp. 34 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner MULL DRILLING CO. INC.  
Lease Name DUSENBURY Well No. 1  
Office Address 6405 East Kellogg Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 4 1957  
Application for plugging filed July 4 1957  
Application for plugging approved July 4 1957  
Plugging commenced July 4 1957  
Plugging completed July 5 1957  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives  
Producing formation None Depth to top Bottom Total Depth of Well 5090 Feet  
Show depth and thickness of all water, oil and gas formations. None

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was filled with heavy rotary mud from TD to 235 ft. Plug set 25 sacks of cement on top of plug put into drill pipe. Heavy mud on top of plug filled up to 40 feet. Plug set 10 sacks of cement on top Pipe cut off three feet below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. Tools  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Harper, ss.  
O. C. Arnott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) O. C. Arnott

SUBSCRIBED AND SWORN to before me this 5 day of July, 1957  
Therese M. Lewis (Address)  
Notary Public.

My commission expires Jan. 7, 1961

PLUGGING  
FILE SEC. 10 T. 34 R. 8W  
BOOK PAGE 26 LINE 14

ROTARY DRILLERS LOG

COMPANY : Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 6-24-57  
 Wichita, Kansas

CONTRACTOR : Mull Drilling Company, Inc. ROTARY DRILLING COMPLETED: 7-4-57  
 Wichita, Kansas

CASING RECORD : Set 8 5/8" @ 240' cemented with 150 sacks cement. LOCATION: Dusenbury #1  
 SE SE NW of Sec. 10-34S-8W  
 Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Clay	20
Red Rock	240
Red Bed	600
Shale & Shells	1050
Shale	1460
Lime & Shale	1775
Lime	2030
Lime & Shale	2315
Shale	2680
Shale & Lime	3485
Sand & Shale	3615
Shale & Lime	4130
Lime	4315
Lime & Shale	4584
Cherty Lime	4620
Lime	4891
Shale	5010
Viola	5057
Simpson	5090' R.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

BY Joseph E. Brungardt, Jr.  
 JOSEPH E. BRUNGARDT, JR.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 10th day of July, 1957.



Madge M. Miller  
 NOTARY PUBLIC

EXPIRES: FEBRUARY 24, 1960.

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 16 1957

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 10 T 34 R 8W  
 BOOK PAGE 26 LINE 14