


15.077-20509-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County. Sec. 6 Twp. 34S Rge. 8W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
C-S/2 SW  
Lease Owner W. L. Kirkman, Inc.  
Lease Name Jones Well No. 1  
Office Address P. O. Box 18611, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Dry Hole  
Date Well completed April 15, 19 79  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced April 15, 19 79  
Plugging completed April 15, 19 79  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,660'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,660 ft. (rotary total depth) to 288 ft. Set plug at 288 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 288 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1979

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sun Oilwell Cementing, Inc.  
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Merle Britting, Agent (~~XXXXXX~~ of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)



SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 79

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY W. L. Kirkman, Inc.

SEC. 6 T. 34S. 8W  
LOC. C-S/2 SW

FARM Jones

NO. 1

COUNTY Harper

ROTARY TOTAL DEPTH 4,660'

COMM. April 7, 1979

COMP. April 15, 1979

CONTRACTOR H-30, Inc. (Rig #3)

ISSUED April 20, 1979

CASING

10 3/4"

8 5/8" Set at 288' cemented w/200 sxs cement

5 1/2"

4 1/2"

ELEVATION 1,307' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	290'
Shale	1,625'
Shale and Lime	3,600'
Lime	3,785'
Lime and Shale	4,134'
Lime	4,247'
Lime and Shale	4,466'
Lime	4,615'
Lime and Shale	4,660'
Rotary Total Depth	4,660'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

*Merle Britting*  
Merle Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 20th day of April, 1979.

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1979  
CONSERVATION DIVISION  
Wichita, Kansas

WILLISON  
NOTARY  
PUBLIC

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982