

15-007-01653-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 2 Twp. 33 Rge. (E) 13 (W)

Location as "NE/CNW&SWK" or footage from lines Center NE SE
Lease Owner Barbara Oil Company
Lease Name Carter Well No. 5
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed July 6, 1955 19
Application for plugging filed Verbally July 6, 1955 19
Application for plugging approved " July 6, 1955 19
Plugging commenced July 6, 1955 19
Plugging completed July 7, 1955 19
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes verbally

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	303'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled from 4550' up to 300' with heavy mud, 1/3 sack hulls, set Halliburton bridge plug at 300', used 20 sacks cement through drill pipe, filled with heavy mud to 35' of top, another 1/3 sack hulls, another bridge plug and 102 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R.C. Patton Company
Address Oppheum Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
R.F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R.F. Ramsey*
322 Central Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 1955
Mildred Fisher
Notary Public.

My commission expires March 2, 1957

PLUGGING
FILE SEC 2 T 33 R 13W
BOOK PAGE 122 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 - 1955
7-8-55
CONSERVATION DIVISION
Wichita, Kansas

15-007-01653-0000

Barbara Oil Company
Carter Well # 5
Comm.
Comp.
Contractor R. C. Patton Co.,

6/21/55
7/7/55

Location Ctr. NE/4 SE/4 Section 2-
T33S-R13W Barber County, Kansas.
CASING RECORD
3 5/8" Casing at 303 Feet.
Cemented with 175 Sacks Cement

Red Bed Rock	303
Red Beds & Shells	750
Gry Shale & Shells	1235
Shale & Shells	1400
Salt & Shale	1500
Shale & Shells	1790
Shale & Lime	3640
Sandy Shale	3752
Shale & Lime 3924	3924
Sandy Shale	3975
Lime	3981
Lime & Shale	4000
Lime	4265
Lime & Shale	4502
Lime	4510
Cherty Lime	4525
Shale & Lime	4550
Total Depth	4550

STATE OF Kansas COUNTY OF Sedgewick ss.

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By Robert W. Patton

Subscribed and sworn to before me this 21st day of July 1955

[Signature]
Notary Public.

My Commission Expires Oct 4th 1958

PLUGGING
PAGE 232 OF 132
BOOK PAGE 132 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1955
7-22-55
CONSERVATION DIVISION
Wichita, Kansas