

15-007-00543-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 2 Twp. 33 Rge. 13 (E) (W) X
Location as "NE/CNW/SW" or footage from lines Center SW NW
Lease Owner Graham-Michaelis Drilling Co.
Lease Name Magnison Well No. #1
Office Address 211 North Broadway, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-3-62 19
Plugging completed 12-8-62 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Depth to top Bottom Total Depth of Well 3833 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back with sand to 3790'. Mixed and ran 5 sacks cement thru dump bailor. Mudded hole to 200' and sat 10' rock bridge. Mixed and ran 20 sacks cement thru dump bailor. Mudded hole to 40' and sat 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

DEC 11 1962
12-11-62
CONSERVATION DIV.
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1962
Erving D. Miller
Notary Public.

My commission expires 24 October 1964



15-007-00543-0000

NO. 1 WMA HARTSON

WELL RECORD

Location: C. SW Hr 2-330-13W
Barber County, Kansas

Commenced: July 28, 1954

Operator: William Graham Oil Company
1005 E. 2nd St., Wichita, Kansas

Completed: August 7, 1954

Elevation: 1648 R.B.

Contractor: Graham-Messman-Rinehart Eng. Co.
1005 E. 2nd, Wichita, Kansas

Production:

Casing Record: 8 5/8" @ 423' w/250 sacks cement
5 1/2" @ 3815' w/50 sacks cement

.....L O O.....

Red bed	160
Red bed - shells	423
Red bed - shells	1060
Shale - shells	1720
Lime - shale	2665
Shale - lime	2765
Shale	2980
Lime - shale	3085
Lime - shale	3115
Shale - shells	3180
Lime	3210
Lime - shale	3355
Lime	3432
Lime - shale	3597
Sand, shale - lime	3600
Lime - shale	3760
Lime - shale	3770
Shale	3817
Douglas	3827
Sand - shale	5833 R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1962
12-12-62
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, GRAHAM-MESSMAN-RINEHART ENGINEERING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART ENGINEERING COMPANY

By: _____
J. A. Gilliland

Subscribed and sworn to before me
this 12th day of August, 1954.

Notary Public

My Commission Expires: September 14, 1957

Wichita, Kansas