


15-007-00542-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber

County. Sec. 2 Twp. 33 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner D.W. Skinner

Lease Name Weidener #1 Well No.

Office Address Medicine Lodge, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 12-8-58 19

Plugging completed 12-12-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp

Producing formation Depth to top Bottom Total Depth of Well 3881 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	302'	none
				5-1/2"	3881'	3092'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3881' and found it open.
Filled w/sand to 3850' and dumped 5 sacks of
cement with bailer. Pulled 5 1/2" casing, cleared
hole and mudded to 200', set rock bridge to 190'
and dumped 20 sacks of cement. Mudded the hole
to 40', set 10' rock bridge and ran 10 sacks of
cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORP

JAN 16 1959
1-16-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF KANSAS COUNTY OF HICE, ss.

I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 58

9-27-62

Thomas V. Meyer

Notary Public.

My commission expires

PLUGGING
FILE SEC 2 T 33 R 130
BOOK PAGE 2 LINE 35

K & S DRILLING, INC. & MAYFAIR MINERALS, INC.
NO. 1 WELLS

Cons. No. 27 Sec. 2-23E-13W
Sedgewick County, Kansas

Casing
5 1/8" Set @ 300'
5 1/2" Set @ 3000'

275' Depth

Comm: 11-28-53
Comp.: 12-8-53
Total Depth: 3000'

FORMATION	DEPTH
Surface clay and red bed	0 - 100
Sand and red bed	100 - 120
Shale and shells	120 - 145
Shale and shells	145 - 200
red bed and shale	200 - 270
Shale and shells	270 - 1300
Shale and shells	1300 - 1560
Lime and shale	1560 - 1600
Lime and shale	1600 - 1705
Lime and shale	1705 - 2000
Lime	2000 - 2075
Lime and shale	2075 - 2200
Lime and shale	2200 - 2375
Lime and shale	2375 - 2700
Lime and shale	2700 - 2750
Sand, shale and lime	2750 - 2770
Lime and shale	2770 - 2800
Sand and shale	2800 - 2870
Sand	2870 - 3000

STATE OF KANSAS }
SEDEWICK COUNTY } SS

I hereby certify that the above information is true and correct to the best of my knowledge.

Walter E. ...

Subscribed and sworn to before me this 11 day of December, 1953.

Walter E. ...
Notary Public



My Commission Expires: October 29, 1955

PLUGGING
FILE SEC. 2 T. 33 R. 13W
BOOK PAGE 2 LINE 35