

lc
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

NOV 28 1962

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: R. R. #2 Great Bend, Kansas.

Lease Name Sterling "B" #1 Well No. #1

Location C W/2 SW NE Sec. 34 Twp. 34 Rge. 13 (E) (W) X

County Barber Total Depth 3646'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: Abandoned oil & gas well.

Plugging Contractor: Southwest Caseing Pulling Co.

Address: Box 364 Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:30 PM Day 26 Month Nov Year 1962

The Above well was plugged as follows:

~~3645' of 4 1/2" long string cemented with 75 sacks cement and 3 sacks gel
Perforated between 3639' and 3642'. Sanded to 3630' and 3 sacks cement.
314' of surface pipe circulated with 200 sacks cement. Hole filled to 200'
with mud, 10' rock bridge and 20 sacks cement. Hole filled to 40' with
mud, 10' rock bridge and 10 sacks cement to base of collar.~~

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/29/62
INV. NO. 6104-2

Signed: Harmon Justice
Well Plugging Supervisor