

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas**RECEIVED**
STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Petroleum Inc.Complete Address: 352 N. Broadway, Wichita, KansasLease Name Roberts "B" Well No. # 1Location NE NW SE Sec. 34 Twp. 34 Rge. 13 (E) (W) WCounty Barber Total Depth 4881Abandoned Oil Well Gas Well X Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Southwest Casing Pulling Co.Address: Box 364, Great Bend, Kansas License No. 399Operation Completed: Hour 5:00 PM Day 5th Month June Year 1963

The Above well was plugged as follows:

304' of 8 5/8" surface pipe, cement circulated with 225 sacks. 3900' of
5 1/2" long string, cemented with 100 sacks. Plugged back to 3790'. Top
perferation 3661'. Sanded to 3650', cemented with 5 sacks. Bailed hole
down to 225', set plug with 10' rock bridge, cemented with 20 sacks.
Filled hole with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar.3269' 66 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICEDDATE 6/4/63INV. NO. 7228-uSigned: Archie Elving
Well Plugging Supervisor